G.MILLER E.STECKLER G.SWOPE

# Test Pit # 1

0-2'	strip mine spoil
2'-3.5'	original topsoil, organic matter, roots – gray, rotted from being covered
3.5'-7'	ML, 10 –20% gravel – seepage at 3.5'
7'-8'	CL / ML, good material for embankments

# Test Pit # 2

05'	top soil, organic matter, leaf litter
.5'-4'	ML / CL, predominately gray, heavily mottled, seepage at 4'
4'-8'	ML/CL, 25% gravel
8'-11'	CL, good material

## Test Pit # 3

05'	topsoil, organic matter, leaf litter
.5'- 1.5'	ML, heavily mottled, seepage at 1.0'
1.5'- 7'	ML / CL, brownish-red, 10% gravel
7'-9'	GM, useable material if mixed in with other layers
9'-13'	CL, gray, very dry

### Test Pit #4

05'	top soil, organic matter, leaf litter
.5'- 2.5'	ML, mottled
2.5'-4.5'	ML / CL, brown, 20% gravel
4.5'- 7.5'	ML / CL, heavily mottled
7.5'- 10.5'	tight, weathered shale, seepage at 7.5

# Test Pit #5

05'	topsoil, organic matter
.5'- 1'	ML, light brown
1'- 3.5'	ML. heavily mottled, seepage at 3'
3.5'-4'	ML, brown, thin layer of shale, 40-50% coarse fragments
4'-8'	ML/CL, gray, < than 10% gravel
8'-9'	Hard shale
9'- 11'	ML, 20-30% gravel, heavy flow of water at 11'