

CONSTRUCTION NOTES

1. THE 6" DIA. SDR-35 PVC PIPE LABELED "TEMPORARY" FOR THE OUTLET PIPE OF THE WETLAND IS TO DIVERT WATER FROM THE TREATMENT BEDS. THIS PIPE SHALL BE PLACED ON THE SURFACE, WITH ADEQUATE SUPPORT, AS THE EXPECTED LENGTH OF OPERATION IS 6 MONTHS OR LESS. THE CONTRACTOR WILL NOT HAVE TO REMOVE THIS PIPE.
2. WATER IS NOT TO BE INTRODUCED INTO THE TREATMENT BEDS UNTIL INOCULATION OF THE BEDS BY ALLEGHENY MINERAL ABATMENT, INC. USING THEIR PATENTED "PYROLUSITE PROCESS".
3. IT IS THE DUTY OF CONTRACTORS TO COMPLY WITH THE PROVISIONS OF PENNSYLVANIA ACT 187 (1996) BEFORE PERFORMING ANY EXCAVATION WORK.

PA ONE CALL SERIAL NO. _____ DATE: _____

LEGEND

---C--- CONSTRUCTION LIMITS
---E--- OVERHEAD ELECTRIC LINE
--o---o-- VARIOUS PIPING (AS LABELED)
O TEST PITS
---D--- DIVERSIONS
ROCK-LINED WATERWAYS
A BENCH MARKS