Remediation Project Descriptive Summary

Name of Project: Cottagetown RAMP

Location (county, township, watershed): Somerset County, Shade Township,

Stonycreek River Watershed

Project Description

The proposed project involves modifying an existing non-functioning passive treatment

system constructed at the Cottagetown RAMP site. In 1988, this system was constructed

to treat a 25 GPM discharge. The proposed modification to the site would be the addition

of a passive alkalinity-generating system to make better use of the passive treatment areas

already constructed on the site.

Water currently leaving the passive treatment system has approximately the same

low ph as the water entering the treatment system. For this reason, the existing passive

treatment system is, in effect, useless. The water leaving this treatment system is also very

high in iron content. The water exiting the existing system then enters Miller Run, the

impacted stream, contaminating its waters with acid and iron.

Both acid and iron have a detrimental effect on aquatic life. Most species of algae

can not exist in acidic water, nor can many rooted aquatic plants. Without algae and other

plants, many insects and fish have no sources of food. Acid water also affects the blood

chemistry of fish. The degree that the fish are affected varies according to the species.

Acid waters usually also contain dissolved metals such as aluminum, cadmium, lead and

manganese that are harmful to aquatic life. For example, aluminum kills fish by damaging

their gills, affecting sodium levels in their blood. Fish eggs are also very susceptible to

high acidity levels. Even if the fish are able to survive some levels of pollution, they

cannot effectively reproduce. In turn, the population eventually dies out.

Another harmful material contained within mine drainage is iron. Iron particles tend to coat the bottom of the waterways, virtually smothering fish eggs and destroying the habitat of bottom-dwelling organisms by filling the nooks and crannies where most aquatic insects live. Miller Run would obviously benefit greatly from the addition of a passive alkalinity-generating system to the Cottagetown RAMP site. The quality of the water leaving the system would improve due to the resulting increase in the ph of the water. Therefore, the water received by Miller Run would be less acidic, thus improving the overall quality of Miller Run, as well as the wildlife living within it.

The project will be implemented according to the following steps: (please refer to the attached as-built drawing)

Step 1: Pond No. 1 will be expanded to the approximate dimensions of 75' x 140' and will be converted to an alkalinity generating system by the addition of compost and limestone.

Step 2: The existing diversion, D₁, will be moved slightly to allow for the expansion of

Pond No's. 1 and 1A. & Pond 2

VFP

Step 3: Pond No. 1A will be enlarged and converted into a sedimentation pond.

Step 4: Additional compost will be added to Pond No. 2

Step 5: The rock present in Pond No. 4 will be removed. This rock will be added to Pond No. 1 if needed.

Expected measurable environmental results include the following: the overall quality of the water leaving the treatment system will be improved because the acidity of the water will be lessened due to counteracting alkalinity generated by this system, the overall visual appearance of the site will be improved, the wildlife habitat will be greatly improved, and Miller Run will be enhanced due to the lesser amounts of acidic water entering it.

As for the relationship of this project to other projects in this watershed, this project is part of the overall SCRIP effort. As stated before, this project is a modification of the existing non-functioning passive treatment system constructed at the Cottagetown RAMP site.

Project Schedule

"Goals and Milestones to be Achieved"

- 1. Project Design
- 2. Engineering
- 3. Contracting
- 4. Construction Inspection
- 5. Post-Construction Monitoring

"Time Schedule for Each Goal"

- 1. Project Design August 1997
- 2. Engineering August 1997
- 3. Contracting December 1997
- 4. Construction / Inspection March December 1998
- 5. Post-Construction Monitoring March December 1998

"Responsible Party for each Goal"

The ENGINEERING and DESIGN of this project will be completed by the Pennsylvania Mountain Service Corps. (AmeriCorps) in cooperation with the NRCS and the Somerset Conservation District. CONTRACTING and CONSTRUCTION INSPECTION will be managed by the Conservation District. POST-CONSTRUCTION MONITORING will be performed by the Conservation District as well.

Budget


"Annual Breakdown of Individual Components (e.g. design, construction, monitoring, personnel, administration, etc.)"

Engineering and Design	\$0.00
Equipment	\$0.00
Supplies	\$4,000.00
Construction	\$60,000.00
Administration	\$6,000.00

[&]quot;Total of the Budget"

The total proposed budget comes to \$70,000.00

The total proposed local match for the project is approximately \$23,500.00 The total estimated project cost is approximately \$93,500.00



Subsidiary of Berwind Natural Resources Corporation

509 FIFTEENTH STREET WINDBER, PENNSYLVANIA 15963 (814) 467-4557 FAX: (814) 467-4559

February 12, 1997

David A. Steele, District Manager Somerset Conservation District 1590 North Center Avenue, Suite 103 Somerset, PA 15501

Re: Cottagetown RAMP Site

Dear Mr. Steele:

Upon your acknowledgement and acceptance of the following terms, this letter will be your authority to enter property owned by Berwind Corporation ("Berwind") and leased to Berwind's affiliate, Wilmore Coal Company, specifically Tract 1099 in Shade Township, Somerset County, to rehabilitate existing acid mine drainage ponds known as the Cottagetown RAMP site. These ponds are located along Township Road 742 as shown on Map No. 3A of 16 attached hereto.

The Somerset Conservation District (SCD) will confine its activities to the area shown in yellow on the attached map.

(2) All disturbed areas will be graded and seeded upon completion of the project.

(3) The SCD will notify Berwind of the beginning and completion dates of work on the project.

(4) Berwind will not be liable for any injuries sustained while work is being performed at the site, and the SCD, its agents, employees and contractors, will indemnify and hold Berwind Corporation and Wilmore Coal Company harmless from and against any claim, loss, damage, expense or liability (including attorneys; fees and other costs incurred in the defense of any claim) resulting to any person or property in or upon said premises by reason of any use which may be made of the premises or any part thereof, or by reason of any act or thing done or omitted to be done in, upon or about the premises or any part thereof.

All work shall be completed by December 31, 1997, unless extended in writing by Berwind.


Jusan J. Moon


Please acknowledge and return one copy of this letter agreement before entering the premises.

> Very truly yours, A. T. Sossong President

The foregoing terms and conditions are acknowledged and accepted this 18th day of February , 1997:

WITNESS:





COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL RESOURCES

PAGE: 1

de Cottage Town - Input

LABORATORY REPORT FOR SAMPLE NUMBER H9639570

RECEIVED 7/23/96 REPORTED 8/14/96

COLLECTOR COLLECTOR NO. 7441038

SO. ALLEGHENIES WATERSHEDS

ESTABLISHMENT QUEMAHOMING CREEK

CASE NAME

SOMERSET SHADE TWP

FACILITY ID COOE

SAMPLING DATE 7/22/96

SAMPLING TIME

STANDARD ANAL 711

TYPE CODE

WON

STREAM CODE

RIVER MILE IND

flow. 30 gpm

Before SAP Constructions

TEST	DESCRIPTION	RESULT	CONC	VERIFY	8Y	VERIFY DATE
00403	PH LAB	3.3000		G	HWS	7/23/96
00410	T ALK CACO3	0.0000	HG/L	G	HVS	7/23/96
00436	PH4	40.0000	MG/L	G	MRD	8/01/96
00900A	T HARD CACO3	315.0000	MG/L	G	DJD	8/13/96
00945A	SO4 TOTAL	273.0000	MG/L	G	EVC	8/01/96
01045A	FE	12000,0000	UG/L	G	MYM	7/25/96
01047A	FERROUS	5040,0000	UG/L	G	MLB	7/26/96
01055A	MN	3040,0000	UG/L	G	MYM	7/25/96
01105A	AL	9030.0000	UG/L	G	МҮМ	7/25/96
70508	T ACIDITY HT	144.0000	MG/L	G	MRD	7/25/96

TOTAL NUMBER OF TESTS FOR THIS SAMPLE 10

INTEROFFICE MEMORANDUM

Date:

03-Mar-1999 01:27am EST

From:

SIS_MANAGER

SIS_MANAGER@DER002@MRGATE@DER0

Dept:

Tel No:

TO: MILAVEC.PAMELA@A1

Subject: FINALRPT:1744102111999538-64.DOC - FINAL REPORT FOR SAMPLE

03/03/1999 12:07:22 AM

Laboratory Report For Abandoned Mine Reclamation

Page: 001

Sample ID:

7441 538 02/11/1999

Status: COMPLETED

Collector: Southern Alleghenies Watersheds

County: NOT INDICATED

State:

Municipality: NOT INDICATED

Location: NOT INDICATED Reason: Routine Sampling

Laboratory Sample ID: I1999006496

Standard Analysis: 711 BASIC AMD - METALS

COMPLETED

Test/CAS# - Description		Reported Results	Completed
00403	PH ALKALINITY Hardness T CALCIUM T MAGNESIUM T SULFATE T IRON T MANGANESE T ALUMINUM T T SUSP SOLID HOT ACIDITY FERROUS IRON	4. pH units	02/17/1999
00410		0.0 MG/L	02/17/1999
00900		202.092 MG/L	02/19/1999
00916A		37.0 MG/L	02/19/1999
00927A		26.6 MG/L	02/19/1999
00945A		194. MG/L	02/19/1999
01045A		6200.0 UG/L	02/19/1999
01055A		2030.0 UG/L	02/19/1999
01105A		2250.0 UG/L	02/19/1999
00530		<2 MG/L	02/24/1999
70508		38.0 MG/L	02/24/1999
01047A		200.0 UG/L	02/26/1999

INFlow After SAP CONSTRUCTION

INTEROFFICE M E M O R A N D U M

Date:

03-Mar-1999 01:27am EST

From:

SIS MANAGER

State:

SIS_MANAGER@DER002@MRGATE@DER0

Dept:

Tel No:

TO: MILAVEC.PAMELA@A1

Subject: FINALRPT:1744102111999539-63.DOC - FINAL REPORT FOR SAMPLE

03/03/1999 12:07:22 AM

Laboratory Report For Abandoned Mine Reclamation

Page: 001

Sample ID: 7441 539 02/11/1999

Status: COMPLETED

Collector: Southern Alleghenies Watersheds

County: NOT INDICATED

Municipality: NOT INDICATED Location: NOT INDICATED

Reason: Routine Sampling

Laboratory Sample ID: I1999006497 Standard Analysis: 711 BASIC AMD - METALS

COMPLETED

Test/CAS# - Description		Reported Results	Completed
00403 00410 00900 00916A 00927A 00945A 01045A 01055A 01105A 70508 00530 01047A	PH ALKALINITY Hardness T CALCIUM T MAGNESIUM T SULFATE T IRON T MANGANESE T ALUMINUM T HOT ACIDITY T SUSP SOLID FERROUS IRON	7.5 pH units 86.0 MG/L 292.778 MG/L 76.9 MG/L 24.4 MG/L 217. MG/L 830.0 UG/L 1080.0 UG/L <200.0 UG/L 0 MG/L <2 MG/L 730.0 UG/L	Completed 02/17/1999 02/17/1999 02/19/1999 02/19/1999 02/19/1999 02/19/1999 02/19/1999 02/19/1999 02/17/1999 02/24/1999 02/26/1999

Out Flow AFTEN SAP Construction