Slippery Rock Watershed Coalition SR109 PASSIVE TREAMENT SYSTEM FACT SHEET

PA Game Lands No. 95, Washington Township, Butler County, PA

FUNDING SOURCE:

EPA 104(b)(3) Grant

PROJECT PARTICIPANTS:

Puryear Excavating and Trucking PA Bureau of District Mining Operations (Knox)

Bureau of Mining and Reclamation PA DEP Northwest Regional Office
PA Game Commission Butler County Conservation District

NRCS WPCAMR

PA Fish and Boat Commission Slippery Rock Watershed Coalition

Slippery Rock University

COMPLETION DATE:

Major construction completed August 1998

Water Quality Monitoring ongoing: PA DEP - Knox DMO

MATERIALS USED FOR TREATMENT:

166 yd³ of compost (1 foot layer)

450 tons of AASHTO No. 1 limestone (3 foot layer)

WATER COLLECTION AND DISTRIBUTION:

<u>Collection</u>: By check dam and rock lined channel.

<u>Inlet</u>: From the collection system, flow is distributed vertically down through a 1 foot layer of compost and then continues down through a 3 foot layer of AASHTO No. 1 limestone to the underdrain system consisting of 3 rows of 6" perforated Schedule 40 PVC connected to a 6" Schedule 40 PVC manifold of the vertical flow system.

<u>Outlet</u>: Flow from the underdrain system rises vertically through 6" Schedule 40 PVC pipes and is discharged to the retention pond/wetland. The current elevation of the outlet of the pipes creates a 4 foot depth of water above the top of the compost. Discharge from the retention pond/wetland is via a rock lined channel to the stream.

SYSTEM DIMENSIONS (FEET):

	<u>Length</u>	<u>Width</u>	<u>Depth</u>
Vertical Flow System	144	91	12
Retention Pond	70	40	5
<u>Wetland</u>	70	40	3

SOIL AMENDMENTS AND SEED MIXTURE:

Birdsfoot trefoil @ 10 lbs/ac; White Dutch clover @ 4 lbs/ac; Reed Canary Grass @ 15

lbs/ac; Winter Wheat cover @ 120 lbs/ac, Aglime @ 10 tons/ac; 10-20-20 fertilizer; straw @ 3 tons/ac

WATER QUALITY (representative):

	<u>Flow(gpm)</u>	<u>рН</u>	<u>alk(mg/l)</u>	<u>acd(mg/l)</u>	<u>Fe(mg/l)</u>	<u> Al(mg/l)</u>
Pre-construction: Raw	14	4.9	9	14	3.1	0
Post-construction: Final	12	7.5	135	0	0	0