

8. ITEMS OF WORK AND CONSTRUCTION DETAILS

Items of work to be performed in conformance with this specification and the construction details therefor are:

A. **Bid Item 3; Pollution Control**

- (1) This item consists of the implementation of the Erosion and Sedimentation Pollution Control Plan as approved by the Elk County Conservation District.
- (2) In addition to the permanent erosion and sedimentation pollution control measures, the contractor shall install temporary controls utilizing acceptable erosion control methods in accordance with the PA DEP Erosion and Sediment Pollution Control Program Manual.

These temporary measures include, but are not limited to:

- a. Limit clearing and grubbing prior to actual need.
 - b. Provide control of access and haul roads including contouring, dust control, and erosion control.
 - c. Stage earthwork activities to minimize accelerated erosion and prevent sediment pollution.
 - d. Temporary mulch areas left unprotected more than 20 working days.
- (3) All Erosion and Sedimentation Control measures shall be inspected after each storm event.
 - (4) In Section 7, Measurement and Payment, Method 3 shall apply.

B. **Bid Item 3A; Silt Fence**

- (1) This item consists of furnishing, installing, maintaining and removing the silt barrier fence as shown on the drawings. The fence shall be 1.5-foot minimum height.
- (2) Sediment shall be removed from behind the fence when it reaches 1/3 of the original above ground height. Any tears or breaks in the fence shall be repaired immediately.
- (3) The silt barrier fence shall meet the requirements of PennDOT Publication 408 (latest edition), Section 865.2. It shall be installed in accordance with Section 865.3.
- (4) In Section 7, Measurement and Payment, Method 1 shall apply.