ABANDONED MINE DRAINAGE REMEDIATION PROJECT FOR THE SILVER CREEK DISCHARGE LOCATED IN

BLYTHE TOWNSHIP, SCHUYLKILL COUNTY, PA

PROJECT

ACT 187 UNDERGROUND UTILITY PROTECTION ACT RETTEW ASSOCIATES, INC. HEREBY STATES THAT, PURSUANT TO THE PROVISIONS OF ACT NO. 287 OF 1974, AS AMENDED BY ACT 187 OF 1996, OF THE PENNSYLVANIA LEGISLATURE, IT HAS PERFORMED THE FOLLOWING IN PREPARING THESE DRAWINGS REQUIRING EXCAVATION OR DEMOLITION WORK AT SITES WITHIN THE POLITICAL SUBDIVISION(S) SHOWN ON THE DRAWINGS:

- 1. PURSUANT TO SECTION 4, CLAUSE (2) OF SAID ACT, RETTEW ASSOCIATES, INC. REQUESTED FROM EACH USER'S OFFICE DESIGNATED ON SUCH LIST PROVIDED BY THE ONE CALL SYSTEM NOTIFICATION, THE INFORMATION PRESCRIBED BY SECTION 2, CLAUSE (4) OF SAID ACT, NOT LESS THAN (10) NOR MORE THAN (90) WORKING DAYS BEFORE FINAL DESIGN IS TO BE COMPLETED.
- 2. PURSUANT TO SECTION 4, CLAUSE (5) OF SAID ACT, RETTEW ASSOCIATES, INC. HAS MET THEIR OBLIGATIONS OF CLAUSE (2) BY CALLING THE ONE CALL SYSTEM SERVING THE LOCATION WHERE EXCAVATION IS TO BE PERFORMED.
- 3. PURSUANT TO SECTION 4, CLAUSE (3) OF SAID ACT, RETTEW ASSOCIATES, INC. HAS SHOWN UPON THESE DRAWINGS "THE POSITION AND TYPE OF EACH LINE, AS DERIVED PURSUANT TO THE REQUEST MADE AS REQUIRED BY CLAUSE (2), THE SERIAL NUMBER PROVIDED BY THE ONE CALL SYSTEM, THE TOLL-FREE ONE CALL SYSTEM PHONE NUMBER, AND THE NAME OF THE USER, THE USER'S DESIGNATED OFFICE ADDRESS AND PHONE NUMBER AS SHOWN ON THE LIST REFERRED TO IN SECTION 4, CLAUSE (5) OF

AND RETTEW ASSOCIATES, INC DOES NOT MAKE ANY REPRESENTATION, WARRANTY, ASSURANCE OR GUARANTEE THAT THE INFORMATION RECEIVED PURSUANT TO SAID REQUEST AND AS REFLECTED ON THESE DRAWINGS IS CORRECT OR ACCURATE, BUT RETTEW ASSOCIATES, INC. IS REFLECTING SAID INFORMATION ON THESE DRAWINGS ONLY DUE TO THE REQUIREMENTS OF THE SAID ACT NO. 187 OF DECEMBER 19, 1996.

ONE CALL SYSTEM SERIAL NO. NOTIFICATION BY RETTEW ASSOCIATES, INC. 08/04/2009

1-800-242-1776

ONE CALL SYSTEM SERIAL NUMBER:

CALL BEFORE YOU DIG! PENNSYLVANIA LAW REOUIRES (3) WORKING DAYS NOTICE FOR **CONSTRUCTION PHASE AND (10) WORKING** DAYS IN DESIGN STAGE - STOP CALL

UTILITIES RESPONDED:

BLYTHE TOWNSHIP MUNICIPAL AUTHORITY 375 VALLEY STREET NEW PHILADELPHIA, PA 17959-1218 CONTACT: MICHAEL E BURDA

BLYTHE TOWNSHIP NEW PHILADELPHIA RD KASKA, PA 17959 CONTACT: GREG KURRILLA

PPL ELECTRIC UTILITIES CORPORATION 4810 LYCOMING MALL DR MONTOURSVILLE, PA 17754 CONTACT: PAM SEITZER E-MAIL: pdseitzer@pplweb.com

SCHUYLKILL COUNTY MUNICIPAL AUTHORITY 221 SOUTH CENTRE STREET POTTSVILLE, PA 17901

CONTACT: DAVID J HOLLEY E-MAIL: dholley.scma@comcast.net

SHEET INDEX

COVER EXISTING PLAN SHT. 3 EXISTING PLAN PROPOSED PLAN PROPOSED PLAN E&SPLAN SHT. 7 E&SPLAN SHT.8 DETAILS **DETAILS DETAILS DETAILS**

DETAILS

SCHUYLKILL VALLEY SEWER AUTHORITY PO BOX 314 MARY D, PA 17952-0314 CONTACT: RON GREENE E-MAIL: suzanneapanavage@verizon.net

VERIZON PENNSYLVANIA INC 201 STANWIX ST 4TH FLOOR PITTSBURGH, PA 15222

CONTACT: OFFICE PERSONNEL

VERIZON PENNSYLVANIA INC 901 TATNALL STREET 2ND FLOOR CONTACT: OFFICE PERSONNEL

PROJECT AREA

LOCATION MAP

APPROXIMATE SCALE: 1"=2000'

SHENANDOAH, DELANO, POTTSVILLE & ORWIGSBURG, PA USGS QUADS

SOILS MAP APPROXIMATE SCALE: 1"=600'

GENERAL NOTES

- BENCHMARK- PK SET IN CONCRETE MANHOLE CONE SECTION, LOCATED NEAREST TO THE SILVER CREEK MINE DISCHARGE POOL. 512960.38 NORTHING 2419170.33 EASTING ELEVATION 798.09
- ALL EXISTING UTILITIES HAVE BEEN SHOWN IN ACCORDANCE WITH THE BEST AVAILABLE INFORMATION.
- 3. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL ABOVE GROUND AND BELOW GROUND UTILITIES AND STRUCTURES AND WILL BE RESPONSIBLE FOR THE PROTECTION OF THESE UTILITIES AND STRUCTURES
- 4. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THE EXISTING UTILITIES AND MAINTAIN UNINTERRUPTED SERVICE AND ANY DAMAGE SHALL BE REPAIRED IMMEDIATELY AND COMPLETELY AT HIS
- 5. THE PLAN LOCATIONS AND DIMENSIONS SHALL BE STRICTLY ADHERED TO UNLESS OTHERWISE DIRECTED BY THE ENGINEER. PLAN CHANGES, SHOULD THEY BE REQUIRED, ARE SUBJECT TO MUNICIPAL AND COUNTY
- 6. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING A COPY OF ALL PERMITS RELATED TO THE CONSTRUCTION SHOWN ON THESE PLANS ON THE JOB SITE AT ALL TIMES.
- 7. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS ON THE PROJECT SITE PRIOR TO THE START OF CONSTRUCTION.

8. CONTRACTOR SHALL NOTIFY ALL UTILITIES REQUIRED PER ACT 187 FOR

- VERIFICATION AND LOCATION OF UTILITIES PRIOR TO CONSTRUCTION. 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL JOB SITE SAFETY, ALL TRAFFIC CONTROL, TRENCH BARRICADING, COVERING, SHEETING AND
- 10. ALL BERMS AND IMPOUNDMENTS SHALL BE CONSTRUCTED IN 6" LIFTS AND
- COMPACTED TO 95% PROCTOR DENSITY. 11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ACCESS TO
- 12. THE LIMESTONE AGGREGATE SHALL CONTAIN NOT LESS THAN NINETY PERCENT (90%) CALCIUM CARBONATE CONTENT, NOT MORE THAN FIVE PERCENT (5%) MAGNESIUM OXIDE (MgO), AND NOT MORE THAN FIVE PERCENT (5%) IRON OXIDE(Fe2O3). A SAMPLE OF THE LIMESTONE MUST BE TESTED BY A THIRD PARTY LABORATORY AND THE RESULTS MUST BE SUBMITTED FOR REVIEW PRIOR TO PLACEMENT OF ANY LIMESTONE.
- SHALL MEET SPECIFICATION SET FORTH IN PENNDOT PUBLICATION 408/2003. CERTIFICATION WILL BE REQUIRED FOR QUALITY AND CLASSIFICATION OF ALL AGGREGATE UTILIZED.
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND DISPOSAL FOR ALL UNUTILIZED MATERIAL ON THE SITE.
- 15. ALL CLAY MATERIAL SHALL BE COMPACTED TO ELIMINATE SEEPAGE. 16. MATERIAL FOR CONSTRUCTION OF BERMS SHALL BE CLEAN FILL, FREE OF
- ORGANIC MATERIAL AND STONES IN EXCESS OF 6" IN DIAMETER.
- 17. TRACKED EQUIPMENT SHALL BE ALLOWED ONSITE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO REPAIR ANY DAMAGE CAUSED BY SUCH
- 18. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING RETTEW ASSOCIATES, INC., AND THE SCHUYLKILL HEADWATERS ASSOCIATION TEN (10) WORKING DAYS PRIOR TO THE START OF CONSTRUCTION.


FOR RETTEW ASSOC	COMEALTH PROFESSIONAL	CHRISTINE HALD	ENGINEER PE073813	NAV IYEMMEN


06-03883-002_graphics 08-04234-001 GIS Base							
IN E. BUBECK, P.E.	СНКО ВҮ: СЕВ	FIELDBOOK NO. DATA COLLECTOR	СНКО ВҮ: СLМ				
N E. I	вү:	HEF: VER	ву:				


 \simeq 0 **L** \mathbf{C} <u>ပ</u> င


SIL AUGUST 6, 2009


DWG. NO. 08-04234-001



















POLYETHYLENE FLARED END SECTION NOT TO SCALE SD\SD035






CROSS-SECTION

OUTLET	PIPE DIA.	TAILWATER CONDITION	MAX FLOW	MAX VELOCITY	APRON LENGTH	APRON WIDTH	RIPRAP SIZE	RIPRAP THICKNESS
FES-1	15"	MIN	12.00	9.80	14'	17'-9"	R-5	27"
FES-3	8"	MIN	5.28	15.13*	10'	12'	R-6	30"
FES-5	8"	MIN	6.34	18.16*	11'	13'	R-6	30"
FES-7	8"	MIN	4.36	12.48	8'	10'	R-6	30"

1. MERGE END SECTION INTO RIPRAPPED SPILLWAYS WHERE REQUIRED. 2. SHOULD REQUIRED SPILLWAY RIPRAP SIZE EXCEED REQUIRED OUTLET PROTECTION RIPRAP USE THE REQUIRED SPILLWAY RIPRAP.


* SEE CALCULATION DOCUMENTS FOR EXPLANATION OF MAXIMUM VELOCITY EXCEEDANCE.

FLARED END SECTION OUTLET PROTECTION




CHANNEL	Bw	d	Z	MIN. SLOPE	MAX. SLOPE	EROSION PROTECTION
OUTLET SWALE	40'	2'	2	8.73%	8.73%	R-3 RIPRAP, 12" THICK
SETTLING POND DIV. TRIANGULAR SEG. 2	0'	2'	2	16.10%	16.10%	R-4 RIPRAP, 18" THICK

RIP-RAP CHANNEL DETAIL



STONE ROADWAY SECTION NOT TO SCALE
PV\PV018




OUTLET	NUMBER OF COLLARS REQUIRED	DISTANCE FROM UPSTREAM END OF PIPE TO 1ST COLLAR	DISTANCE BETWEEN COLLARS
AERATION POND DRAINPIPE	4	12'	20'
SETTLING POND DRAINPIPE	4	8'	21'
WETLAND CELL DRAINPIPE	1	8'	N/A
VARIABLE LEVEL POND DRAINPIPE	2	8'	21'


NOTES:

1. SEE BASIN EMBANKMENT DETAIL FOR LOCATION WITHIN BERM. 2. APPLY MASTIC TO CONNECTING BANDS AND SET IN PLACE. BOLT HALVES
TOGETHER & INSTALL METAL BANDS ON SPLIT HALVES OF COLLAR. TIGHTEN BOLTS
AND BANDS. APPLY MASTIC AS NEEDED TO INSURE GOOD SEAL. BACKFILL AND
HAND TAMP.

ANTI-SEEP COLLAR-POLYETHYLENE NOT TO SCALE SD\SD054

CLAY DIKE SHALL CONSIST OF CLAY CONTAINING NO MORE THAN 15% (BY VOLUME) STONE NO LARGER THAN TWO (2) INCHES IN DIAMETER. CLAY SHALL BE PLACED IN SIX (6) INCH LIFTS AND COMPACTED BY A MECHANICAL TAMPER TO NOT LESS THAN 95% OF MAXIMUM DENSITY AT OPTIMUM MOISTURE CONTENT.





RIPRAP STREAMBANK STABILIZATION

-12" THICK R-3 RIPRAP (VARIABLE LEVEL POND)

TYPE 3 GEOTEXTILE FABRIC

TYPE 3 GEOTEXTILE FABRIC

APRON APRON RIPRAP RIPRAP

R-3 LIMESTONE RIP-RAP

LENGTH WIDTH SIZE THICKNESS

S = 0.00%

PROFILE

3.0' TEMP. SED. BASIN #1

VARIABLE LEVEL POND = 30'

<u>SECTION</u>

OUTLET


VARIABLE LEVEL POND

EMERGENCY SPILLWAY


NOT TO SCALE SD\SD026

)' VARIABLE LEVEL PÖND

UPSTREAM FACE



TYPICAL TRENCH DETAIL



TYPICAL BACKFILL (NON-PAVED AREAS) NO SCALE

CLASSIFICATION OF MATERIALS:

CLASS 1 — THIS MATERIAL SHALL CONSIST OF 2A COARSE AGGREGATE OR 2 RC STONE FREE OF SLAG, EXCEPT IN WET OR UNSTABLE AREAS WHERE THE BEDDING MAY BE NO. 8 OR NO. 57 COARSE AGGREGATE. ALL MATERIALS SHALL CONFORM TO PennDOT PUBLICATION 408, SECTION 703.3.


CLASS 1S - THIS MATERIAL SHALL CONSIST OF NO. 8 COARSE AGGREGATE FREE OF SLAG, EXCEPT IN WET OR UNSTABLE AREAS WHERE THE BEDDING MAY BE NO. 8 OR NO. 57 COARSE AGGREGATE. ALL MATERIALS SHALL CONFORM TO PennDOT PUBLICATION 408, SECTION 703.3.

CLASS 2 - THIS MATERIAL SHALL CONSIST OF EXCAVATED MATERIAL FREE FROM CINDERS, ASHES, REFUSE, VEGETABLE OR ORGANIC MATERIAL, BOULDERS, ROCKS NO LARGER THAN FOUR (4) INCHES IN DIMENSION, STONE OR OTHER MATERIAL WHICH IN THE OPINION OF THE ENGINEER IS UNSUITABLE.

OUTLET	LENGTH WIDTH SIZE THICKNESS
SCOUR POOL	R-3 LIMESTONE RIP-RAP 12"
AERATION POND (1)	R-3 LIMESTONE RIP-RAP 12"
SETTLING POND	R-3 LIMESTONE RIP-RAP 12"
MAINTAINED WETLAND CELL	R-3 LIMESTONE RIP-RAP 12"

NOTES:


(1) SEE SHEET 9 FOR AERATION POND SPILLWAY DETAIL.





DISCHARGE **CREE**I DETAILS SILVER

Ш

AUGUST 6, 2009 SHEET NO. ___8__ OF ___12_ DWG. NO. 08-04234-001








SCALE: NTS

NOTE:

1. PLACE CLAY DIKES AT 5' AND 10' FROM THE BOREHOLE AND
EVERY 25' THRERAFTER ALONG 15" INFLUENT PIPE.



TREATED 2"x6" BOARDS


FRONT-UPSTREAM VIEW


- NOTES:

 1. ALL CONCRETE SHALL BE COATED WITH COAL TAR EPOXY COATING.
- 2. CONTRACTOR SHALL SUPPLY 2 S.S. LOCKING BOLTS, NUTS & WASHERS PER STRUCTURE.
- 3. CONTRACTOR SHALL SUPPLY SEVEN 6' TREATED 2"X6" BOARDS PER STRUCTURE.
- 4. CONTRACTOR SHALL SUPPLY TWO 3'-3" TREATED 2"X6" BOARDS PER STRUCTURE WITH $\frac{1}{2}$ " HOLES DRILLED $5\frac{1}{2}$ " APART TO MATCH THE LOCKING ANGLE ON TOP OF THE STRUCTURE.
- 5. REINFORCING DESIGN SHALL BE BY PRE-CASTER.

WETLAND WATER LEVEL CONTROL STRUCTURES

NOT TO SCALE





ABANDONED MINE DRAINAGE REMEDIATION PROJECT
FOR THE
SILVER CREEK DISCHARGE
DETAILS SHEET

DATE: AUGUST 6, 2009

SHEET NO. 10 OF 12

DWG. NO. 08-04234-001

EROSION & SEDIMENT POLLUTION CONTROL NOTES:

<u>STANDARD SEDIMENT AND EROSION CONTROL PLAN NOTES</u>

102.2(A) "THIS CHAPTER REQUIRES PERSONS PROPOSING OR CONDUCTING EARTH DISTURBANCE ACTIVITIES TO DEVELOP. IMPLEMENT AND MAINTAIN BMPS TO MINIMIZE THE POTENTIAL FOR ACCELERATED EROSION AND SEDIMENTATION.

102.4(B)(3) "THE EROSION AND SEDIMENT CONTROL PLAN SHALL BE PREPARED BY A PERSON TRAINED AND EXPERIENCED IN EROSION AND SEDIMENT CONTROL METHODS AND TECHNIQUES, AND SHALL BE

1. VEHICLES AND EQUIPMENT MUST ENTER AND EXIT THE CONSTRUCTION SITE VIA THE ROCK CONSTRUCTION ENTRANCE LOCATED ON FURNACE ROAD.

DESIGNED TO MINIMIZE THE POTENTIAL FOR ACCELERATED EROSION AND SEDIMENTATION."

- 2. STOCKPILE HEIGHTS MUST NOT EXCEED 35 FEET. STOCKPILE SLOPES MUST BE 2:1 OR FLATTER.
- 3. THE OPERATOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IS PROPERLY AND COMPLETELY IMPLEMENTED.
- 4. UNTIL THE SITE ACHIEVES FINAL STABILIZATION, THE OPERATOR SHALL ASSURE THAT THE BMPS ARE IMPLEMENTED, OPERATED, AND MAINTAINED PROPERLY AND COMPLETELY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL BMP FACILITIES. THE OPERATOR WILL MAINTAIN AND MAKE AVAILABLE TO SCHUYLKILL CONSERVATION DISTRICT COMPLETE, WRITTEN INSPECTION LOGS OF ALL THOSE INSPECTIONS. ALL MAINTENANCE WORK, INCLUDING CLEANING, REPAIR, REPLACEMENT, REGARDING, AND RESTABILIZATION SHALL BE PERFORMED IMMEDIATELY.
- . IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BMPS TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT
- 6. BEFORE INITIATING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE SCHUYLKILL CONSERVATION DISTRICT.
- 7. THE OPERATOR SHALL ASSURE THAT AN EROSION AND SEDIMENT CONTROL PLAN HAS BEEN PREPARED, APPROVED BY THE SCHUYLKILL CONSERVATION DISTRICT, AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL SOIL AND/OR ROCK SPOIL AND BORROW AREAS, REGARDLESS OF THEIR
- 8. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG DISCHARGING OVER NON-DISTURBED AREAS.
- 9. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF THE APPENDIX 64. EROSION CONTROL RULES AND REGULATIONS. TITLE 25. PART 1. DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUBPART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL.
- 10. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES.

102.4(B)(5)(I) "THE EXISTING TOPOGRAPHIC FEATURES OF THE PROJECT SITE AND THE IMMEDIATE SURROUNDING AREA."

11. THE E&S CONTROL PLAN MAPPING MUST DISPLAY A PA ONE CALL SYSTEM INCORPORATED SYMBOL INCLUDING THE SITE IDENTIFICATION NUMBER. (THIS IS A NUMBERED SYMBOL NOT A

102.4(B)(5)(VII) "A SEQUENCE OF BMP INSTALLATION AND REMOVAL IN RELATION TO THE SCHEDULING OF EARTH DISTURBANCE ACTIVITIES, PRIOR TO, DURING AND AFTER EARTH DISTURBANCE ACTIVITIES." 102.4(B)(4) 'EARTH DISTURBANCE ACTIVITIES SHALL BE PLANNED AND CONDUCTED TO MINIMIZE THE EXTENT AND DURATION OF EARTH DISTURBANCE."

102.22(A) "UPON COMPLETION OF AN EARTH DISTURBANCE ACTIVITY OR ANY STAGE OR PHASE OF AN ACTIVITY, THE SITE SHALL BE IMMEDIATELY SEEDED, MULCHED OR OTHERWISE PROTECTED FROM ACCELERATED FROSION AND SEDIMENTATION.

- 12. ONLY LIMITED DISTURBANCE WILL BE PERMITTED TO PROVIDE ACCESS TO THE SITE FOR GRADING AND ACQUIRING BORROW TO CONSTRUCT BMPS. E&SPCPM PG 168
- 13. EROSION AND SEDIMENT BMPS MUST BE CONSTRUCTED. STABILIZED. AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMPS. E&SPCPM PG 168
- 14. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMPS MUST BE STABILIZED
- 15. AT LEAST 7 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL INVITE ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LANDOWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENT CONTROL PLAN PREPARER, AND THE SCHUYLKILL CONSERVATION DISTRICT TO AN ON-SITE MEETING. ALSO, AT LEAST 3 DAYS BEFORE TARTING ANY EARTH DISTURBANCE ACTIVITIES. ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INCORPORATED AT 1-800-242-1776 FOR BURIED UTILITIES LOCATIONS.
- 16. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE CONSTRUCTION SEQUENCE. EACH STAGE SHALL BE COMPLETED BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE.
- 17. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE. THE OPERATOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES DURING NON-GERMINATING PERIODS MUICH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.
- 18. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS.

SEDIMENT BASINS

IMMEDIATELY. E&SPCPM PG 168

19. SEDIMENT BASINS MUST BE PROTECTED FROM UNAUTHORIZED ACTS OF THIRD PARTIES. OTHER BMPS (SPECIFY)

20.AT STREAM CROSSINGS, 50' BUFFER AREAS SHOULD BE MAINTAINED. ON BUFFERS, CLEARING, SOD DISTURBANCES, EXCAVATION, AND EQUIPMENT TRAFFIC SHOULD BE MINIMIZED. ACTIVITIES SUCH AS STACKING LOGS, BURNING CLEARED BRUSH, DISCHARGING RAINWATER FROM TRENCHES, WELDING PIPE SECTIONS, REFUELING AND MAINTAINING EQUIPMENT SHOULD BE ACCOMPLISHED OUTSIDE OF BUFFERS.

TEMPORARY STABILIZATION AND PERMANENT STABILIZATION

- 21. HAY OR STRAW MULCH MUST BE APPLIED AT 3.0 TONS PER ACRE.
- 22.MULCH WITH MULCH CONTROL NETTING OR EROSION CONTROL BLANKETS MUST BE INSTALLED ON ALL SLOPES 3:1 AND STEEPER.
- 23.STRAW MULCH SHALL BE APPLIED IN LONG STRANDS, NOT CHOPPED OR FINELY BROKEN.

102.4(B)(5)(X) "A MAINTENANCE PROGRAM WHICH PROVIDES FOR INSPECTION OF BMPS ON A WEEKLY BASIS AND AFTER EACH MEASURABLE RAINFALL EVENT, INCLUDING THE REPAIR OF THE BMPS TO ENSURE EFFECTIVE AND EFFICIENT OPERATION.

- 24.UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT CONTROL BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGARDING, RESEEDING, REMULCHING, AND RENETTING, MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENT CONTROL BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED. E&SPCPM PG 168
- 25. SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED, OR PLACED IN TOPSOIL STOCKPILES.

102.4(B)(5)(XI) 'PROCEDURES WHICH ENSURE THAT THE PROPER MEASURES FOR THE RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THE PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH THIS TITLE."

26. THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PENNSYLVANIA CODE 260.1 ET SEQ., 271.1 ET SEQ., AND 287.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP, OR DISCHARGE ANY BUILDING MATERIAL OR WASTES AT THE SITE."

GENERAL SEDIMENT AND EROSION CONTROL METHODS/PROCEDURES

- 1. IN ALL CASES, THE SMALLEST PRACTICAL AREA OF STABLE LAND SURFACE SHALL BE DISTURBED.
- 2. UTILITY EXCAVATIONS SHALL BE OPEN ONLY LONG ENOUGH TO PROPERLY INSTALL AND INSPECT ALL UNDERGROUND FACILITIES IN ACCORDANCE WITH APPLICABLE SPECIFICATIONS.
- 3. EXCAVATED MATERIAL (SPOIL) SHALL BE PLACED UP SLOPE FROM THE EXCAVATION WHENEVER POSSIBLE. RUNOFF FROM SPOIL PILES SHALL BE DIRECTED THROUGH A SEDIMENT FILTER STRUCTURE AND DISCHARGED IN A NON-EROSIVE MANNER.
- BACKFILLED EXCAVATIONS SHALL BE RESTORED TO ORIGINAL TYPE OF COVER AND GRADE AS PER SPECIFICATIONS. SEEDING SHALL BE DONE ACCORDING TO SCHEDULE FOR PERMANENT SEEDING. TEMPORARY STABILIZATION IS REQUIRED FOR ANY AND ALL ERODIBLE/SOLUBLE AREAS AND MATERIALS TO BE EXPOSED.
- 5. LAWN AREAS SHALL BE FINISHED GRADED WITH 6-INCHES OF TOPSOIL UNLESS OTHERWISE NOTED. POSITIVE DRAINAGE SHALL BE MAINTAINED AWAY FROM ALL STRUCTURES. NO ISOLATED LOW
- 6. SEDIMENT SPILLED, DROPPED OR TRACKED ONTO PAVED SURFACES SHALL BE REMOVED IMMEDIATELY.
- 7. AT THE END OF EACH WORKING DAY, ANY SEDIMENT TRACKED OR CONVEYED ONTO A PUBLIC ROADWAY WILL BE REMOVED AND RE-DEPOSITED ONTO THE CONSTRUCTION SITE. REMOVAL CAN BE COMPLETED THROUGH USE OF MECHANICAL OR HAND TOOLS, BUT MUST NEVER BE WASHED OFF THE ROAD BY USE OF WATER.
- FILTER FABRIC FENCE MUST BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE SECTION MUST EXTEND AT LEAST 8' UPSLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.
- 9. ANY FENCE SECTION, WHICH HAS BEEN UNDERMINED OR TOPPED, MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. (SEE ROCK FILTER OUTLET DETAIL.)
- 10. WHERE ENDS OF FILTER FABRIC COME TOGETHER, THEY MUST BE OVERLAPPED, FOLDED AND STAPLED TO PREVENT SEDIMENT BYPASS. THE TOE ANCHOR MUST BE BACKFILLED AND COMPACTED TO A DENSITY EQUAL TO THE SURROUNDING SOILS.
- 11. DIVERSION CHANNELS, SEDIMENTATION BASINS, AND STOCKPILES MUST BE STABILIZED IMMEDIATELY.
- 12. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLETS.
- 13. THE HEIGHT OF THE ROCK FILTER SHOULD EQUAL 5/6 THE HEIGHT OF THE STRAW BALES OR FILTER FABRIC.
- 14. ROCK CONSTRUCTION ENTRANCE THICKNESS WILL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE OF ROCK MATERIAL WILL BE MAINTAINED ON THE SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PUBLIC ROADWAYS WILL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE.

RESTORATION OF PLANTING AREAS

- 1. IF EARTH DISTURBANCE OCCURS DURING THE MONTHS OF NOVEMBER THROUGH MARCH, THEN AROOSTOOK WINTER RYE SHALL BE APPLIED TO DISTURBED AREAS AS A TEMPORARY SEED MIXTURE. IF STABILIZATION CANNOT BE ACHIEVED WITH AROOSTOOK WINTER RYE, THEN MULCH WITH TACKIFIER SHALL BE APPLIED TO DISTURBED AREAS. MULCH SHALL BE CLEAN OAT OR WHEAT STRAW AND SHALL BE APPLIED AT THE RATE OF 3 TONS PER ACRE. TACKIFIER SHALL BE APPLIED AT THE MANUFACTURER'S APPLIED RATE. AREAS THAT LOSE THE MULCH COVER SHALL BE REMULCHED.
- FINAL RESTORATION SHALL BE PERFORMED NO LATER THAN THE START OF THE NEXT PLANTING SEASON FOLLOWING CONSTRUCTION. THE PLANTING SEASON SHALL BE AS ESTABLISHED BY THE U.S. AGRICULTURAL SERVICE FOR THE AREA OF CONSTRUCTION.
- TOPSOIL SHALL BE FREE FROM SUBSOIL, BRUSH, WEEDS, OR OTHER LITTER, CLAY LUMPS AND STONES, BUT MAY CONTAIN DECAYING VEGETABLE MATTER AS IS PRESENT IN GOOD TOPSOIL.
- 4. PRECAUTIONS SHALL BE EXERCISED AS NECESSARY TO CONFORM WITH LAWS RELATING TO EROSION AND SEDIMENT CONTROL.
- SEED SHALL BE NOT MORE THAN TWO (2) YEARS OLD. GERMINATION TESTS OF SEEDS SHALL BE MADE NOT MORE THAN SIX (6) MONTHS PRIOR TO SEEDING. SEED THAT HAS BECOME WET, MOLDY, OR OTHERWISE DAMAGED SHALL NOT BE USED.
- 6. ALL SEED MIXTURES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO SEEDING.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO PRODUCE A STAND OF GRASS IN ALL SEEDED OR SODDED AREAS. EROSION, DROUGHT, OR ANY OTHER CONDITION ENCOUNTERED SHALL NOT RELIEVE THE CONTRACTOR OF THIS REQUIREMENT.

SEEDING NOTES: TEMPORARY

MULCH - CLEAN OAT OR WHEAT STRAW SHALL BE FREE FROM MATURE SEED-BEARING STALKS OR ROOTS OF PROHIBITED OR NOXIOUS WEEDS AS DEFINED BY THE PENNSYLVANIA SEED ACT OF 1947. APPLY AT A RATE 3 TONS PER ACRE. PRECAUTIONS SHALL BE TAKEN TO STABILIZE THE MULCH UNTIL THE VEGETATIVE COVER IS ESTABLISHED.

SEED MIXTURE SHALL BEAR A GUARANTEED STATEMENT OF ANALYSIS AND SHALL BE COMPOSED OF THE VARIETIES FOLLOWING AND MIXED IN THE PROPORTIONS SPECIFIED.

TEMPORARY SEED MIXTURE	PROPORTION BY WEIGHT	MINIMUM PURITY	MINIMUM GERMINATIO
KENTUCKY 31 TALL FESCUE	75%	95%	80%
RYEGRASS OR RED FESCUE	25%	95%	80%

THREE-PERCENT REDTOP MAY BE ADDED TO THE LAWN MIXTURE ON SLOPE AREAS OR FOR LATE SPRING OR LATE FALL SEEDING.

TEMPORARY SEEDING SHALL BE APPLIED AT THE RATE OF ONE (1) POUND PER THOUSAND (1,000) SQUARE FEET.

ALL AREAS TO BE SEEDED SHALL BE LOOSENED TO A DEPTH OF AT LEAST TWO INCHES BY MECHANICAL

MULCH SEEDED AREAS IMMEDIATELY AFTER SEEDING. LIMESTONE AND FERTILIZER SHALL BE APPLIED UNIFORMLY TO AREAS TO BE SEEDED, AND WORKED INTO THE SOIL TO A DEPTH OF 2".

LIMESTONE - PULV. AG. LIMESTONE - 40 LBS./1000 S.F.

FERTILIZER - 10-10-10 FERTILIZER - 12.5 LBS./1000 S.F.

SEEDING - SEED ALL DISTURBED AREAS WITH THE TEMPORARY SEED MIXTURE. SEEDING SHALL OCCUR MARCH 15-JUNE 15 OR AUGUST 15- OCTOBER 15, UNLESS OTHERWISE DIRECTED BY THE ENGINEER. MULCH (HAY OR STRAW) SHALL BE APPLIED AT A RATE OF 3 TONS PER ACRE DURING THE NON-GERMINATING PERIOD OF OCTOBER 15-MARCH 15.

<u>SEEDING NOTES:</u> PERMANENT

ALL TOPSOIL SHALL BE LOOSENED TO A DEPTH OF AT LEAST 4". ALL OBJECTIONABLE MATERIAL LARGER THAN 2" SHALL BE REMOVED.

DUE TO THE NATURE OF THE SOILS AT THE SITE IT MAY BE NECESSARY TO IMPORT TOPSOIL WITH SUFFICIENT ORGANIC MATERIAL AND WATER CAPACITY TO SUSTAIN THE SPECIFIED SEED MIXTURE. LIMESTONE AND FERTILIZER SHALL BE APPLIED UNIFORMLY TO AREAS TO BE SEEDED, AND WORKED INTO THE SOIL TO A DEPTH OF 6".

LIMESTONE - GREATER OF RATE DETERMINED BY SOIL TEST OR 6 TONS PER ACRE FERTILIZER - 10-10-20 (NITROGEN SLOW RELEASE - PHOSPHATE - POTASH) FERTILIZER - GREATER OF RATE DETERMINED BY SOIL TEST OR 1,000 LBS. PER ACRE

MULCH OF LONG STEM STRAW SHALL BE APPLIED AT EVEN APPLICATION OF 3 TONS PER ACRE WITH A SURFACE COVERAGE OF 80-90%.

SEED MIXTURES

1) TYPE SM - FOR AREAS OF 3:1 SLOPE AND STEEPER

2) TYPE WS 1 - FOR AREAS FLATTER THAN 3:1 SLOPE

SEEDING NOTES: PERMANENT (CONTINUED)

TYPE SM SEED MIXTURE	MAXIMUM WEED SEED PERCENT	MINIMUM QUANTITY PURE LIVE SEED LBS./ACRE
ORCHARDGRASS, DACTYLIS GLOMERATA (AXIOM, ABLE, BENCHMARK, DAWN, HALLMARK, HAYMATE, POTOMAC, RANCHO OR STERLING)	0.25	20
WEEPING LOVEGRASS, ERAGROSTIS CURVULA (COMMON)	0.25	6
PERENNIAL RYEGRASS, LOLIUM PERENNE (COMMON)	0.50	20
BIRDSFOOT TREFOIL, LOTUS CORNICULATUS (DAWN, EMPIRE, VIKING, FERGUS, NORCEN OR TRETANA)	0.25	10
FIELD BROMEGRASS, BROMUS ARVENSIS (COMMON) -OR-	0.25	14
SMOOTH BROMEGRASS, BROMUS INERMIS (VNS)	0.25	14
SPRING OATS (BLAZE, ARMOR, HERCULES, PORTER OR VNS) -OR-	0.25	10
WNTER WHEAT (TYLER, DYNASTY, FREEDOM, MADISON OR VNS) -OR-	0.25	10
WINTER RYE (COMMON OR VNS)	0.25	<u>10</u>
TOTAL POUNDS PER ACRE		<u>80</u>

TYPE WS 1 SEED MIXTURE	MAXIMUM WEED SEED <u>PERCENT</u>	MINIMUM QUANTITY PURE LIVE SEED LBS./ ACRE
BIG BLUESTEM, ANDROPOGON GERARDII (PAWNEE, KAW, CHAMP, NIAGARA OR ROUNDTREE)	2	10
<u>LITTLE BLUESTEM.</u> SCHIZACHYRIUM SCOPARIUM (ALDOUS, BLAZE CAMPER OR CIMARRON)	2	8
<u>SAND DROPSEED.</u> SPOROBOLUS CRYPTANDRUS (COMMON OR VNS)	2	0.1
REDTOP, AGROSTIS GIGANTEAN ROTH (COMMON OR VNS)	0.25	5
WHITE DUTCH CLOVER, TRIFOLIUM REPENS (COMMON OR VNS)	0.25	5
<u>SPRING OATS</u> (BLAZE, ARMOR, HERCULES, PORTER OR VNS) -OR-	0.25	25
WINTER WHEAT (TYLER, DYNASTY, FREEDOM, MADISON OR VNS) -OR-	0.25	25
WINTER RYE (COMMON OR VNS)	0.25	<u>25</u>
TOTAL POUNDS PER ACRE		<u>53.1</u>

THE QUANTITY OF SEED WILL BE DETERMINED BY CALCULATING THE PERCENT OF PURE LIVE SEED (PLS). PLS IS DETERMINED BY MULTIPLYING THE MINIMUM PURITY PERCENT BY THE MINIMUM GERMINATION PERCENT AND DIVIDING BY 100.

SUBJECT TO THE APPROVAL OF THE ENGINEER, THE CONTRACTOR MAY ADD OTHER GRASS SEEDS TO THE TYPE SM AND TYPE WS1 SEED MIXTURES TO SECURE A COVER CROP. BUT NO ADDITIONAL PAYMENT WILL BE MADE THEREFORE.

NO SEED SHALL CONTAIN ANY OF THE FOLLOWING NOXIOUS WEED SEEDS: CANADA THISTLE, FIELD BINDWEED, JOHNSON GRASS, PERENNIAL PEPPERGRASS, PERENNIAL SOW THISTLE, QUACK GRASS, HORSE NETTLE, BEDSTRAW, CORN COCKLE, BRASSICA KABER, BRASSICA NIGRA, WILD ONION OR

ALL SEED SHALL CONFORM TO THE PENNSYLVANIA SEED ACT OF 1965, ACT NO. 187, AS AMENDED, AND REGULATIONS OF THE PENNSYLVANIA DEPARTMENT OF AGRICULTURE, BUREAU OF PLANT INDUSTRY

CERTIFICATION OF PURITY AND GERMINATION ANALYSIS MUST BE SUPPLIED UNDER THE CURRENT RULES FOR TESTING SEEDS OF THE ASSOCIATION OF OFFICIAL SEED ANALYSTS BY THE COMMONWEALTH OF PENNSYLVANIA, DEPARTMENT OF AGRICULTURE, BUREAU OF PLANT INDUSTRY.

ALL SEED FURNISHED SHALL BE FULLY TAGGED AND DELIVERED BY INDIVIDUAL VARIETIES, SEPARATELY PACKAGED OR BAGGED. ALL PRE-MIXED SEED SHALL HAVE AN INSPECTION TAG, STAMPED. DATED AND SIGNED BY THE DEPARTMENT INSPECTOR. SEWN INTO THE INSIDE TOP OF EACH BAG. NO SEED SHALL BE UTILIZED WHICH HAS A MIX DATE OLDER THAN NINE (9) MONTHS NO SEED SHALL BE USED ON ANY PROJECT UNLESS IT HAS BEEN INSPECTED AND SAMPLED AS DESCRIBED, OR SAMPLED BY INDIVIDUAL SPECIES AND MIXED ON THE PROJECT SITE UNDER DEPARTMENT SUPERVISION.

THE SEED FURNISHED SHALL NOT BE MORE THAN TWO (2) YEARS OLD AND SHALL HAVE BEEN TESTED FOR GERMINATION NOT MORE THAN SIX (6) MONTHS PRIOR TO SEEDING OPERATIONS. A CERTIFICATE OF TEST RESULTS SHALL BE FURNISHED TO THE RESIDENT ENGINEER BEFORE APPROVAL FOR USE OF THE SEED IS GIVEN.

SEED, WHICH HAS BECOME WET, MOLDY OR OTHERWISE DAMAGED IN TRANSIT OR STORAGE, WILL NOT BE ACCEPTED.

THE INOCULANT FOR TREATING LEGUMINOUS SEED SHALL BE A STANDARD COMMERCIAL PRODUCT CONSISTING OF A SUITABLE CARRIER, CONTAINING A CULTURE OF NITROGEN-FIXING BACTERIA SPECIFICALLY FOR THE SEED TO BE INOCULATED. ALL CONTAINERS MUST REMAIN SEALED UNTIL CONTENTS ARE USED IN THEIR ENTIRETY. INOCULANT SHALL NOT BE USED AFTER THE EXPIRATION DATE INDICATED ON THE CONTAINER.

SUITABLE STORAGE IN A MODERATE TEMPERATURE SHALL BE PROVIDED AT ALL TIMES. ALL INOCULANT SHALL BE SUBJECT TO APPROVAL OF THE RESIDENT ENGINEER.

ALL LEGUMINOUS SEED WITH THE EXCEPTION OF THE BLACK LOCUST TREE SEED SHALL BE INOCULATED OR TREATED WITH AN APPROVED CULTURE AS RECOMMENDED BY THE SUPPLIER. THE SEED SHALL THEN BE SOWN WITHIN TWENTY-FOUR (24) HOURS AFTER TREATMENT. IF SEED IS TO BE APPLIED BY HYDRAULIC SEEDERS. FOUR (4) TIMES THE MANUFACTURER'S RECOMMENDED AMOUNT OF INOCULANT SHALL BE USED. INOCULANT MUST BE KEPT AT TEMPERATURES BELOW 75°

THE INOCULANT SHALL BE VIABLE AND MADE UP OF SEVERAL BACTERIAL STRAINS WHICH ARE SPECIFIED FOR THE LEGUME GROUP TO BE INOCULATED. INOCULANT SHALL NOT BE USED LATER THAN THE DATE INDICATED ON THE CONTAINER OR SPECIFIED BY THE SUPPLIER.

CONSTRUCTION SEQUENCE

- 1. AT LEAST SEVEN DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL INVITE ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LANDOWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENT CONTROL PLAN PREPARER, AND THE SCHUYLKILL CONSERVATION DISTRICT TO AN ON-SITE MEETING. ALSO, AT LEAST THREE DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PA ONE CALL SYSTEM AT 1-800-242-1776 FOR BURIED UTILITIES LOCATIONS.
- 2. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE.
- 3. INSTALL ROCK CONSTRUCTION ENTRANCE AT LOCATION WHERE CONSTRUCTION VEHICLES WILL BE ENTERING AND LEAVING THE SITE. ALL VEHICLES ENTERING THE SITE SHALL DO SO VIA THE ROCK CONSTRUCTION ENTRANCE. CONTRACTOR SHALL NOT TRACK MUD OR SEDIMENT ONTO ANY PAVED AREAS OR PUBLIC ROADS. ANY MUD OR SEDIMENT TACKED ONTO ROADWAYS
- SHALL BE REMOVED BY THE CONTRACTOR AT THE END OF EACH WORKING DAY. WASHING OF THE ROADWAY IS NOT PERMITTED. 4. INSTALL SILT FENCE THROUGHOUT THE ENTIRE SITE AS INDICATED ON THE EROSION AND SEDIMENTATION CONTROL PLAN.
- 5. CLEAR AND GRUB IN THE AREA OF THE TEMPORARY SEDIMENT BASIN AS INDICATED ON THE PLANS. CONSTRUCT THE VARIABLE LEVEL POND WETLAND WATER LEVEL CONTROL STRUCTURE, CLAY CORE BERM, EMERGENCY SPILLWAY, AND RIP—RAP OUTLET PROTECTION. THE WETLAND WATER LEVEL CONTROL STRUCTURE WILL BE THE PRINCIPAL SPILLWAY FOR THE SEDIMENT BASIN. THE CONTRACTOR SHALL ENSURE THE SEDIMENT BASIN IS STABILIZED (SEEDED AND MULCHED) AND FUNCTIONING PROPERLY PRIOR TO ANY FURTHER EARTH DISTURBANCE ACTIVITIES. CONTRACTOR SHALL CONTACT THE SCHUYLKILL CONSERVATION DISTRICT TO INFORM THEM THE SEDIMENT BASIN HAS BEEN COMPLETED.
- 6. CLEAR AND GRUB THE AREA FOR THE WETLAND CELL UPSLOPE OF THE TEMPORARY SEDIMENT BASIN.
- 7. STOCKPILE TOPSOIL AT THE DESIGNATED LOCATION AND SURROUND WITH 18" SILT FENCE. SEED STOCKPILE AS PER TEMPORARY SEEDING SPECIFICATIONS. STRIPPED TOPSOIL SHALL BE STOCKPILED WITH SIDE SLOPES NO GREATER THAN 3:1. EXCAVATED MATERIAL SHALL NOT BE PLACED WITHIN 50 FEET OF A STREAM, WETLAND, OR OTHER WATERS OF COMMONWEALTH.
- 8. EXCAVATE AS NECESSARY FOR INSTALLATION OF THE WETLAND CELL CLAY CORE BERMS, POND DRAIN PIPE AND APPURTENANCES. CONSTRUCT THE DOWNSLOPE BERM FOR THE WETLAND CELL AS WELL AS COMPLETING THE BERM IN BETWEEN WETLAND CELL AND THE VARIABLE LEVEL POND. CONSTRUCT THE BROAD CRESTED SPILLWAY TO ENSURE WATERS FLOWING INTO THE WETLAND CELL FLOW INTO THE TEMPORARY SEDIMENT BASIN BEFORE DISTURBING ANY UPHILL AREAS. COMPLETE THE GRADING OPERATIONS FOR THE BOTTOM OF THE CELL AND APPLY STABILIZATION (SEEDED, MULCHED, AND SPECIAL WETLAND MIXTURE AS NEEDED).
- 9. ONCE THE DOWNSTREAM BERM AND SPILLWAY HAVE BEEN CONSTRUCTED FOR THE WETLAND CELL, THE AREA DESIGNATED FOR THE SETTLING POND CAN BEGIN.
- 10. EXCAVATE AS NECESSARY FOR INSTALLATION OF THE SETTLING POND CLAY CORE BERMS, POND DRAIN PIPE AND APPURTENANCES. CONSTRUCT THE DOWNSLOPE BERM FOR THE SETTLING POND AS WELL AS COMPLETING THE BERM IN BETWEEN THE SETTLING POND AND THE WETLAND CELL. CONSTRUCT THE BROAD CRESTED SPILLWAY WITH CONCRETE CURB TO ENSURE WATERS FLOWING INTO THE SETTLING POND AREA FLOWS INTO THE TEMPORARY SEDIMENT BASIN BEFORE DISTURBING ANY UPHILL AREAS. COMPLETE THE GRADING OPERATIONS FOR THE BOTTOM OF THE POND AND APPLY STABILIZATION (SEEDED AND MULCHED).
- 11. ONCE THE DOWNSTREAM BERM AND SPILLWAY HAVE BEEN CONSTRUCTED FOR THE SETTLING POND, THE AREA DESIGNATED FOR THE AERATION POND AND SCOUR POOL CAN BEGIN.
- 12. EXCAVATE AS NECESSARY FOR INSTALLATION OF THE AERATION POND AND SCOUR POOL CLAY CORE BERMS, POND DRAIN PIPE AND APPURTENANCES. CONSTRUCT THE DOWNSLOPE BERM FOR THE AERATION POND AS WELL AS COMPLETING THE BERM IN BETWEEN THE AERATION POND AND THE SETTLING POND. CONSTRUCT AND INSTALL THE BROAD CRESTED SPILLWAY TO ENSURE WATERS FLOWING INTO THE AERATION POND AREA FLOWS INTO THE TEMPORARY SEDIMENT BASIN AS SHOWN ON THE PLANS. COMPLETE THE GRADING OPERATIONS FOR THE BOTTOM OF THE POND AND THE REST OF THE BERM AND APPLY STABILIZATION (SEEDED AND MULCHED).
- 13. THE EXCAVATION OF THE SCOUR POOL AND GRADING OPERATIONS FOR THE BERM CAN COMMENCE ALONG WITH THE CONSTRUCTION OF THE AERATION POND. THE SCOUR POOL LIMESTONE RIPRAP SHALL BE INSTALLED ONCE FINAL STABILIZATION HAS BEEN ACHIEVED THROUGHOUT THE SITE. ONCE ALL DOWNSTREAM PONDS HAVE BEEN CONSTRUCTED AND STABILIZED, THE
- 14. INSTALL THE INFLUENT PIPING INCLUDING THE OUTLET PROTECTION, GATE VALVE, AND CONCRETE ENCASING FOR THE SEWER LINE PIPE CROSSING AS SHOWN ON THE PLAN UP TO AND INCLUDING THE DROP MANHOLE STRUCTURE. THE INFLUENT VALVES SHALL BE MAINTAINED IN THE CLOSED POSITION EXCEPT FOR NECESSARY TESTING OF THE VALVES. ADDITIONALLY, THE CONTRACTOR SHALL PREVENT SEDIMENT, DEBRIS, STONES, ETC. FROM WASHING INTO THE INFLUENT PIPING DURING CONSTRUCTION.
- 15. INSTALL THE REMAINDER OF THE INFLUENT PIPING AND THE INFLUENT STRUCTURE WHILE BACKFILLING THE INFLUENT PIPES WITH CLAY DIKES AS INDICATED.
- 16. INSTALL THE BROAD DIP DIVERSION SWALE OVER THE INFLUENT PIPE AS SHOWN ON THE PLAN. THIS DIVERSION SWALE WILL DIRECT WATER FLOWING DOWN THE ACCESS ROADWAY INTO THE CURRENT MINE DISCHARGE CHANNEL BELOW THE INFLUENT STRUCTURE TO BYPASS THE TREATMENT SYSTEM. THIS SWALE SHOULD BE IMMEDIATELY STABILIZED TO PERMANENT CONDITION WITH THE REMAINING RIPRAP FROM THE ROCK CONSTRUCTION ENTRANCE OR ADDITIONAL STONE.
- 17. FINAL GRADE, SEED MULCH AND STABILIZE AS REQUIRED THE AREA BETWEEN THE SILVER CREEK AMD DISCHARGE AND SILVER CREEK.
- 18. FINAL GRADE, PERMANENTLY SEED, MULCH, AND STABILIZE ANY REMAINING DISTURBED AREAS. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND
- SUBSURFACE CHARACTERISTICS SUFFICIENT TO SLIDING AND OTHER MOVEMENTS. 19. PRIOR TO SEDIMENT BASIN DECOMMISSIONING, THE CONTRACTOR SHALL CONTACT THE SCD. CONVERT THE TEMPORARY SEDIMENT BASIN INTO THE VARIABLE LEVEL POND BY FIRST DRAINING THE POND AND REMOVING AND PROPERLY DISPOSING THE ACCUMULATED SEDIMENT. THE BOARDS IN THE SEDIMENT BASIN OUTLET STRUCTURE SHALL BE REMOVED DOWN TO ITS

OWEST WEIR LEVEL. ANY DISTURBED AREAS DURING SEDIMENT REMOVAL SHALL BE PERMANENTLY SEEDED AND MULCHED ACCORDING TO THE SEEDING SPECIFICATION. UPON CONVERTING

20. UPON SITE STABILIZATION AND CONSERVATION DISTRICT APPROVAL, REMOVE REMAINING EROSION CONTROL MEASURES. ANY AREAS DISTURBED BY REMOVAL OF CONTROLS SHALL BE IMMEDIATELY REPAIRED, STABILIZED AND PERMANENTLY SEEDED AS SHOWN ON THE EROSION AND SEDIMENTATION CONTROL PLAN.

HE SEDIMENT BASIN, ALL THE AGRI DRAIN AND GATE VALVE STRUCTURES SHALL BE SET TO THEIR PERMANENT POSITIONS EXCEPT FOR THE INFLUENT GATE VALVE.

- 21. UNTIL SUCH TIME AS THE SITE IS PERMANENTLY STABILIZED, ALL EROSION AND SEDIMENTATION CONTROLS MUST BE MAINTAINED IN WORKING ORDER. MAINTENANCE MUST INCLUDE
- 22. ONCE ALL EROSION AND SEDIMENT CONTROLS HAVE BEEN REMOVED, WITH THE ENGINEER'S AND CONSERVATION DISTRICT'S APPROVAL, THE INFLUENT GATE VALVE CAN BE OPENED TO ALLOW THE ABANDONED MINE DRAINAGE TO ACTIVELY FILL THE SYSTEM. THE CLIENT, ENGINEER, AND CONSERVATION DISTRICT SHALL BE INVITED TO ATTEND THE OPENING OF THE REMEDIATION FACILITY

RESPONSIBILITIES FOR FILL MATERIALS INCLUDING DEFINITION OF ENVIRONMENTAL DUE DILIGENCE & CLEAN FILL

INSPECTION OF ALL EROSION AND SEDIMENTATION CONTROLS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS.

IF THE SITE WILL NEED TO HAVE FILL IMPORTED FROM AN OFF SITE LOCATION. THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND THE DETERMINATION OF CLEAN FILL WILL IN MOST CASES RESIDE WITH THE OPERATOR. IF THE SITE WILL HAVE EXCESS FILL THAT WILL NEED TO BE EXPORTED TO AN OFF SITE LOCATION, THE RESPONSIBILITY OF CLEAN FILL DETERMINATION AND ENVIRONMENTAL DUE DILIGENCE RESTS ON THE APPLICANT.

APPLICANTS AND/OR OPERATORS MUST USE ENVIRONMENTAL DUE DILIGENCE TO ENSURE THAT THE FILL MATERIAL ASSOCIATED WITH THIS PROJECT QUALIFIES AS CLEAN FILL. DEFINITIONS OF CLEAN FILL AND ENVIRONMENTAL DUE DILIGENCE ARE PROVIDED BELOW. ALL FILL MATERIAL MUST BE USED IN ACCORDANCE WITH THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL", DOCUMENT NUMBER 258-2182-773. A COPY OF THIS POLICY IS AVAILABLE ONLINE AT WWW.DEPWEB.STATE.PA.US. UNDER THE HEADING QUICK ACCESS ON THE LEFT SIDE OF THE SCREEN, CLICK ON "FORMS AND PUBLICATIONS." ON THE LEFT SIDE OF THE SCREEN CLICK ON "TECHNICAL GUIDANCE DOCUMENTS -FINAL." THEN TYPE THE DOCUMENT NUMBER 258-2182-773 INTO THE SEARCH WINDOW AND CONDUCT THE SEARCH. CLICK ON "MANAGEMENT OF FILL."

CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR

CLEAN FILL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE: FILL MATERIALS AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE STILL QUALIFIES AS CLEAN FILL PROVIDED THE TESTING REVEALS THAT THE FILL MATERIAL CONTAINS CONCENTRATIONS OF REGULATED SUBSTANCES THAT ARE BELOW THE RESIDENTIAL LIMITS IN TABLES FP-1A AND FP-1B FOUND IN THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL"

ANY PERSON PLACING CLEAN FILL THAT HAS BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE MUST USE FORM FP-001 TO CERTIFY THE ORIGIN OF THE FILL MATERIAL AND THE RESULTS OF THE ANALYTICAL TESTING TO QUALIFY THE MATERIAL AS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE OWNER OF THE PROPERTY RECEIVING THE FILL. A COPY OF FORM FP-001 CAN BE FOUND AT THE END OF THESE INSTRUCTIONS.

ENVIRONMENTAL DUE DILIGENCE: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS. ANALYTICAL TESTING. ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE.

FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE

PCSWM OPERATION AND MAINTENANCE SCHEDULE

- 1. THE PROPERTY OWNER SHALL OWN, MAINTAIN AND BE RESPONSIBLE FOR ALL STORM WATER MANAGEMENT AND PERMANENT BMP FACILITIES THAT ARE LOCATED OUTSIDE OF STREET RIGHT-OF-WAYS AS PROPOSED ON THIS POST CONSTRUCTION STORM WATER MANAGEMENT PLAN.
- 2. THE OWNER SHALL CONDUCT A VISUAL INSPECTION OF ALL STORM WATER MANAGEMENT AND PERMANENT BMP FACILITIES AT LEAST ONCE EVERY THREE MONTHS AND IMMEDIATELY AFTER STORM EVENTS. SUCH VISUAL EXAMINATION SHALL AT LEAST INVOLVE AN EXAMINATION OF THE STORM WATER COLLECTION. CONVEYANCE AND DETENTION/BMP FACILITIES FOR DEBRIS DEPOSITION (SUCH DEBRIS MAY INCLUDE, BUT SHALL NOT BE LIMITED TO AGGREGATE MATERIAL, LEAVES, GRASS CLIPPINGS, SOIL AND TRASH), AND AN EXAMINATION OF THE STORM WATER DETENTION/BMP FACILITY FOR SOIL AND STRUCTURAL SETTLEMENT, DEPRESSIONS, SINKHOLES, SEEPS, STRUCTURAL CRACKING, ANIMAL BURROWS, EXCESSIVE VEGETATION, CLOGGING, EROSION AND FOUNDATION
- 3. THE OWNER SHALL REMOVE ANY ACCUMULATION OF DEBRIS AND REPAIR ANY DAMAGE TO THE STORM WATER MANAGEMENT AND PERMANENT BMP FACILITIES. REPAIRS SHALL BE MADE USING MATERIAL THAT MEETS OR EXCEEDS THE SPECIFICATIONS PROVIDED ON THE PLANS.
- 4. IN ACCORDANCE WITH THE NPDES PERMIT, THE OWNER IS REQUIRED TO MAINTAIN A RECORD OF ALL INSPECTIONS, REPAIRS AND MAINTENANCE ACTIVITIES ASSOCIATED WITH THE STORM WATER MANAGEMENT AND PERMANENT BMP FACILITIES AT THIS PROJECT SITE. THE OWNER SHALL IMMEDIATELY NOTIFY THE MUNICIPALITY AND THE CONSERVATION DISTRICT PRIOR TO INITIATING ANY MAJOR REPAIR ACTIVITIES (SUCH AS REPAIRS THAT MAY BE REQUIRED AS A RESULT OF SETTLEMENT, SINKHOLES, SEEPS, STRUCTURAL CRACKING OR FOUNDATION MOVEMENT).
- 5. THE OWNER SHALL ALSO COMPLY WITH ANY OTHER MAINTENANCE NOTES THAT MAY BE ON THESE

001-001-001-


ш 2


⋖ C

ك $\mathbf{\alpha}$ C 2 ш S

AUGUST 6, 2009 SHEET NO. ____11__ OF ___12

DWG. NO. 08-04234-001







IN POOLS WITH DEPTHS EXCEEDING 7', THE TOP OF THE PLYWOOD BAFFLE DOES NOT NEED TO EXTEND TO THE TEMPORARY RISER CREST.


	BAFFLE		TEMPORARY RISER	ВОТТОМ
BASIN NO.	LENGTH BAI (FT)	HEIGHT	CREST ELEV TRCE (FT)	BOTTOM ELEV BE (FT)
1	2 @ 225 1 @ 175'	2.75'	760.75	758.00

BAFFLES




SKIMMER ATTACHMENT NOT TO SCALE ES\ES005






JOINING FENCE SECTIONS




WHERE ENDS OF FILTER FABRIC COME TOGETHER, THEY MUST BE OVERLAPPED, FOLDED AND STAPLED TO PREVENT SEDIMENT BYPASS. THE TOE ANCHOR MUST BE BACKFILLED AND COMPACTED TO A DENSITY EQUAL TO THE SURROUNDING SOILS. * STAKES SPACED @ 8' MAXIMUM. USE 2" X 2" WOOD OR EQUIVALENT STEEL STAKES. FILTER FABRIC FENCE MUST BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE BARRIER MUST BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE GROUND ANY SECTION OF FILTER FABRIC FENCE WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET. SEE DETAIL "ROCK FILTER

STANDARD FILTER FABRIC FENCE (18" HIGH) NOT TO SCALE ES\DEP019




OUTLET CROSS—SECTION



UP-SLOPE FACE


ROCK FILTER OUTLETS SHALL ONLY BE USED AS A REPLACEMENT FOR A SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET. STONE SHALL BE REMOVED AND REPLACED WHEN CLOGGED WITH SEDIMENT.

ROCK FILTER OUTLETS NOT TO SCALE ES\DEP018



MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE.

ROCK CONSTRUCTION ENTRANCE



1. FILTER BAGS MAY BE USED TO FILTER WATER PUMPED FROM DISTURBED AREAS PRIOR TO DISCHARGING TO WATERS OF THE COMMONWEALTH. THEY MAY ALSO BE USED TO FILTER WATER PUMPED FROM THE SEDIMENT STORAGE AREAS OF SEDIMENT BASINS.


2. THE PUMPING RATE SHOULD BE DETERMINED BY THE CONTRACTOR BASED UPON ACTUAL AMOUNT OF GROUNDWATER ENCOUNTERED DURING CONSTRUCTION. PUMPING RATES WILL VARY DEPENDING ON THE SIZE OF THE FILTER BAG, AND THE TYPE AND AMOUNT OF SEDIMENT DISCHARGED TO THE

3. FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STICHTED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS.


DISPOSAL PURPOSES MUST BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. 5. BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT

POSSIBLE, A GEOTEXTILE FLOW PATH SHALL BE PROVIDED. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. 6. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE

MANNER SPECIFIED BY THE MANUFACTURER AND SECURLY CLAMPED. 7. THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHOULD BE FLOATING AND SCREENED.



PLAN VIEW



PUMPED WATER FILTER BAG NOT TO SCALE ES\DEP026

SHEET NO. 12 OF 12 DWG. NO. 08-04234-001

 \simeq

4

HS

ا م

ыz **با**

CR E&

S

AUGUST 6, 2009