

6. ITEMS OF WORK AND CONSTRUCTION DETAILS

Items of work to be performed in conformance with this specification and the construction details therefor are:

A. **Bid Item 19; Rock-lined Waterway**

- (1) This item consists of constructing the channels and the furnishing and installation of rock lining and geotextile for all rock-lined waterways as shown on the drawings.
- (2) The rock gradation shall comply with the requirements of NSA No. R-3 graded riprap stone with a maximum size of 6", an average size of 3", and a minimum size of 2".
- (3) The typical section shall be as shown on the drawings.
- (4) The exact location shall be determined and marked on site by the NRCS representative at the time of construction.
- (5) Measurement and Payment -
For items of work, for which specific unit prices are established in the contract, the length of rock-lined waterway will be determined to the nearest linear foot by measurement along the centerline of the waterway. Such payment will constitute full compensation for all labor, materials, equipment and all other items necessary and incidental to the performance of the work.
- (6) Items of work subsidiary to this item are:
 - (a) **Geotextile** – see Section 2, **MATERIALS**, of this specification.